BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT54282

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/18/2022-23, Date: 04-11-2022

Name of Work:Improvements to footpaths in cross roads of Kodigehalli in ward no 12 - Kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of VETTAIKENAR PONNUSWAMY ( )	
				In Figures	In Words
1	438.24	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.	Cum	168.39	Rupees One Hundred Sixty Eight and Thirty Nine Paise Only
2	29.88	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	5946.73	Rupees Five Thousand Nine Hundred Forty Six and Seventy Three Paise Only
3	1.3446	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications.	Tonne	93543.74	Rupees Ninety Three Thousand Five Hundred Forty Three and Seventy
4	956.16	Removing and Resetting of Footpath Slab and pointing in C.M (1:3)	Sqm	193.4	Rupees One Hundred Ninety Three and Forty
5	239.04	Providing B S slabs of selected quality roughly dressed having a size of 10 cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete. as directed by the Engineer in Charge of the work	Sqm	688.85	Rupees Six Hundred Eighty Eight and Eighty Five Paise Only
6	239.04	Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per m2 over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level , including cost of materials, labour and Usage charges of machinery complete as per specifications.	Sqm	1036.57	Rupees One Thousand Thirty Six and Fifty Seven Paise Only
7	956.16	Removing and resetting of cobble stones	Sqm	312.74	Rupees Three Hundred Twelve and Seventy Four
8	398.4	Removing and resetting of kerb stones	m	97.11	Rupees Ninety Seven and Eleven Paise Only
9	119.52	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately)Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates	Cum	5207.29	Rupees Five Thousand Two Hundred Seven and Twenty Nine Paise Only
10	99.6	Providing and fixing pre cast solid cement concrete kerb stones made out of M20 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete as directed by the Engineer in Charge of the work	Nos	417.26	Rupees Four Hundred Seventeen and Twenty Six Paise Only
11	348.6	Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces	Sqm	76.95	Rupees Seventy Six and Ninety Five Paise Only
12	994.406	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km	t.km	86.91	Rupees Eighty Six and Ninety One Paise Only

V. Ponn

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ ವಿಭಾಗ
ಬೃ.ಬೆ.ಮ.ಪಾ., ಬೆಂಗಳೂರು